

BuildQuote AI

AI Powered Construction Estimation & BOQ System

Phone	+254 700 000000
Email	info@buildquoteai.com
Location	Kenya
Registration	Construction Contractor

Quotation No	BQA-9412
Date	14 July 2026
Client	flavian
Project	housemart
County	Migori
House Type	Maisonette
Roof Type	Mabati
Wall Material	Clay Bricks

Bill of Quantities

Description	Qty	Unit	Rate	Amount
Excavation	46.08	m³	900.00	41,472.00
Hardcore Filling	5.76	m³	3,200.00	18,432.00
Blinding Concrete	1.92	m³	8,500.00	16,320.00
Foundation Concrete	9.6	m³	17,000.00	163,200.00
Backfilling	28.8	m³	700.00	20,160.00
Damp Proof Course (DPC)	64.0	m	180.00	11,520.00
Anti-Termite Treatment	240.0	m²	120.00	28,800.00
Clay Bricks	1711	Pieces	55.00	94,105.00
Cement	34	Bags	850.00	28,900.00
Sand	5.64	m³	2,500.00	14,100.00
Walling Labour	20.0	Days	1,800.00	30,840.00
Mabati Sheets	99	Sheets	950.00	94,050.00
Roof Timber	8.28	m³	1,200.00	9,936.00
Ridge Caps	7	Pieces	900.00	6,300.00
Roof Nails	22.1	Kg	350.00	7,735.00
Roof Labour	24.8	Days	0.00	57,860.00
Internal Plaster	192.0	m²	450.00	86,400.00

Description	Qty	Unit	Rate	Amount
External Plaster	192.0	m²	450.00	86,400.00
Wall Putty	192.0	m²	120.00	23,040.00
Wall Paint	384.0	m²	350.00	134,400.00
Floor Screed	240.0	m²	280.00	67,200.00
Floor Tiles	240.0	m²	1,800.00	432,000.00
Ceiling Boards	84	Pieces	900.00	75,600.00
Branding	300.0	Metres	350.00	105,000.00
Ceiling Paint	240.0	m²	350.00	84,000.00
Finishes Labour	24.0	Days	2,200.00	52,800.00
Electrical Cable	300	Metres	120.00	36,000.00
PVC Conduit	300	Metres	70.00	21,000.00
Sockets	28	Pieces	650.00	18,200.00
Switches	22	Pieces	450.00	9,900.00
Light Fittings	24	Pieces	1,800.00	43,200.00
Distribution Board	1	Piece	8,500.00	8,500.00
Electrical Labour	6.0	Days	2,500.00	15,000.00
Water Pipes	150	Metres	250.00	37,500.00
Waste Pipes	90	Metres	280.00	25,200.00
Toilets	4	Pieces	9,500.00	38,000.00
Wash Basins	4	Pieces	4,200.00	16,800.00
Kitchen Sink	1	Piece	8,500.00	8,500.00
Shower Mixers	4	Pieces	3,200.00	12,800.00
Floor Traps	8	Pieces	950.00	7,600.00
Plumbing Labour	6.0	Days	2,200.00	13,200.00
External Doors	2	Pieces	18,000.00	36,000.00
Internal Doors	10	Pieces	8,500.00	85,000.00
Windows	20	Pieces	6,500.00	130,000.00
Door Frames	12	Pieces	2,200.00	26,400.00
Door Locks	12	Pieces	1,800.00	21,600.00
Installation Labour	8.0	Days	2,500.00	20,000.00

Material Summary

: 94105.0, 'cement_cost': 28900, 'sand_cost': 14100.0}

'concrete_volume_m3': 0, 'ridge_caps': 7, 'roof_nails_kg': 22.1}
boards': 84, 'brandering': 300.0}
s': 22, 'light_points': 24, 'distribution_board': 1, 'cable_cost': 36000.0, 'conduit_cost': 21000.0, 'socket_cost': 18200.0, 'switch_cost': 990
'kitchen_sink': 1, 'shower_mixers': 4, 'floor_traps': 8, 'water_pipe_cost': 37500.0, 'waste_pipe_cost': 25200.0, 'toilet_cost': 38000.0, 'bas
12, 'locks': 12, 'external_cost': 36000.0, 'internal_cost': 85000.0, 'window_cost': 130000.0, 'frame_cost': 26400.0, 'lock_cost': 21600.0}

Subtotal	KES 2,420,970.00
VAT 16%	KES 387,355.20
TOTAL PROJECT COST	KES 2,808,325.20

Prepared By	Client Approval
_____	_____
BuildQuote AI	flavian

Generated automatically by BuildQuote AI